

PHYSICS

Real-time antiproton annihilation vertexing with submicrometer resolution

Michael Berghold^{1†}, Davide Orsucci², Francesco Guatieri^{1,3,4,*†}, Sara Alfaro⁵, Marcis Auzins⁶, Benedikt Bergmann^{7,8}, Petr Burian^{7‡}, Roberto Sennen Brusa^{3,4}, Antoine Camper⁹, Ruggero Caravita^{3,4}, Fabrizio Castelli^{10,11}, Giovanni Cerchiari¹², Roman Jerzy Ciuryło¹³, Ahmad Chehaimi^{3,4}, Giovanni Consolati^{10,14}, Michael Doser¹⁵, Kamil Eliaszk¹⁶, Riley Craig Ferguson^{3,4}, Matthias Germann¹⁵, Anna Giszczak¹⁶, Lisa Glögler¹⁵, Łukasz Graczykowski¹⁶, Malgorzata Grosbart¹⁵, Natali Gusakova^{15,17}, Fredrik Gustafsson¹⁵, Stefan Haider¹⁵, Saiva Huck^{15,18}, Christoph Hugenschmidt¹, Malgorzata Anna Janik¹⁶, Tymoteusz Henryk Januszek¹⁶, Grzegorz Kasprowicz¹⁹, Kamila Kempny¹⁶, Ghanshyambhai Khatri²⁰, Łukasz Kłosowski¹³, Georgy Kornakov¹⁶, Valts Kruminis^{6,15}, Lidia Lappo¹⁶, Adam Linek¹³, Sebastiano Mariazzi^{3,4}, Pawel Moskal^{21,22}, Dorota Nowicka¹⁶, Piyush Pandey^{21,22}, Daniel Pęcak^{16,23}, Luca Penasa^{3,4}, Wojtech Petracek²⁴, Mariusz Piwiński¹³, Stanislav Pospisil⁷, Luca Povo^{3,4}, Francesco Prelz¹⁰, Sadiqali Rangwala²⁵, Tassilo Rauschendorfer^{14,15,26}, Bharat Rawat^{27,28}, Benjamin Rienäcker²⁷, Volodymyr Rodin²⁷, Ole Røhne⁹, Heidi Sandaker⁹, Sushil Sharma^{21,22}, Petr Smolyanskiy⁷, Tomasz Sowiński²³, Dariusz Tefelski¹⁶, Theodoros Vafeiadis¹⁵, Marco Volponi^{3,4,14,15}, Carsten Peter Welsch^{27,28}, Michal Zawada¹³, Jakub Zielinski¹⁶, Nicola Zurlo^{29,30}, AEGIS Collaboration§

Copyright © 2025 The Authors, some rights reserved; exclusive licensee American Association for the Advancement of Science. No claim to original U.S. Government Works. Distributed under a Creative Commons Attribution License 4.0 (CC BY).

Primary goal of the AEGIS experiment is to precisely measure the free fall of antihydrogen within Earth's gravitational field. To this end, cold (≈ 50 K) antihydrogen will traverse a two-grid moiré deflectometer before annihilating onto a position-sensitive detector, which shall determine the vertical position of the annihilation vertex relative to the grids with micrometric accuracy. Here, we introduce a vertexing detector based on a modified mobile camera sensor and experimentally demonstrate that it can measure the position of antiproton annihilations within $0.62^{+0.40}_{-0.22}$ μm , a 35-fold improvement over the previous state of the art for real-time antiproton vertexing. These methods are directly applicable to antihydrogen. Moreover, the sensitivity to light of the sensor enables in situ calibration of the moiré deflectometer, substantially reducing systematic errors. This sensor emerges as a breakthrough technology toward the AEGIS scientific goals and will constitute the basis for the development of a large-area detector for conducting antihydrogen gravity measurements.

INTRODUCTION

General relativity currently stands as the prevailing paradigm for understanding gravity and any departure from it would require a fundamental reevaluation of our understanding of physics. At its core lies the weak equivalence principle (WEP), postulating the equality of gravitational and inertial mass and thus the universality

of free fall. The WEP has been tested across various materials to very high precision through Eötvös-type experiments (1, 2). Testing the WEP with antimatter presents a formidable challenge due to the difficulty of producing abundant low-energy antiparticles and the susceptibility to stray electromagnetic fields (3, 4). The idea that antimatter should adhere to the WEP is supported both by

¹Research Neutron Source Heinz Maier-Leibnitz (FRM II), Technical University of Munich, Lichtenbergstr. 1 Garching bei München, 85748 Bayern Germany. ²Institute of Communications and Navigation, German Aerospace Centre (DLR), Münchener Str. 20, 82234 Weßling, Germany. ³Department of Physics, University of Trento, via Sommarive 14, 38123 Povo, Trento, Italy. ⁴TIFPA/INFN Trento, via Sommarive 14, 38123 Povo, Trento, Italy. ⁵Department of Physics, University of Siegen, Walter-Flex-Straße 3, 57072 Siegen, Germany. ⁶Department of Physics, University of Latvia, Raina boulevard 19, LV-1586 Riga, Latvia. ⁷Institute of Experimental and Applied Physics, Czech Technical University in Prague, Husova 240/5, 110 00, Prague 1, Czech Republic. ⁸Faculty of Electrical Engineering, University of West Bohemia, Pilsen, Univerzitní 8, 301 00 Pilsen, Czech Republic. ⁹Department of Physics, University of Oslo, Sem Sælandsveit 24, 0371 Oslo, Norway. ¹⁰INFN Milano, via Celoria 16, 20133 Milano, Italy. ¹¹Department of Physics "Aldo Pontremoli," University of Milano, via Celoria 16, 20133 Milano, Italy. ¹²Institut für Experimentalphysik, University of Innsbruck, Technikerstrasse 25, 6020 Innsbruck, Austria. ¹³Institute of Physics, Faculty of Physics, Astronomy, and Informatics, Nicolaus Copernicus University in Toruń, Grudziadzka 5, 87-100 Toruń, Poland. ¹⁴Department of Aerospace Science and Technology, Politecnico di Milano, via La Masa 34, 20156 Milano, Italy. ¹⁵Physics Department, CERN, 1211 Geneva 23, Switzerland. ¹⁶Faculty of Physics, Warsaw University of Technology, ul. Koszykowa 75, 00-662 Warsaw, Poland. ¹⁷Department of Physics, NTNU, Norwegian University of Science and Technology, Trondheim, Norway. ¹⁸Institute for Experimental Physics, Universität Hamburg, 22607 Hamburg, Germany. ¹⁹Faculty of Electronics and Information Technology, Warsaw University of Technology, ul. Nowowiejska 15/19, 00-665 Warsaw, Poland. ²⁰Systems Department, CERN, 1211 Geneva 23, Switzerland. ²¹Marian Smoluchowski Institute of Physics, Jagiellonian University, Kraków, Poland. ²²Centre for Theranostics, Jagiellonian University, Kraków, Poland. ²³Institute of Physics, Polish Academy of Sciences, Aleja Lotników 32/46, PL-02668 Warsaw, Poland. ²⁴Czech Technical University, Prague, Břehová 7, 11519 Prague 1, Czech Republic. ²⁵Raman Research Institute, C. V. Raman Avenue, Sadashivanagar, Bangalore 560080, India. ²⁶Felix Bloch Institute for Solid State Physics, Universität Leipzig, 04103 Leipzig, Germany. ²⁷Department of Physics, University of Liverpool, Liverpool L69 3BX, UK. ²⁸The Cockcroft Institute, Daresbury, Warrington WA4 4AD, UK. ²⁹INFN Pavia, via Bassi 6, 27100 Pavia, Italy. ³⁰Department of Civil, Environmental, Architectural Engineering and Mathematics, University of Brescia, via Branze 43, 25123 Brescia, Italy.

*Corresponding author. Email: fguatier@cern.ch.

†These authors contributed equally to this work.

‡Present address: Faculty of Electrical Engineering, University of West Bohemia in Pilsen, Univerzitní 8, 301 00 Pilsen, Czech Republic.

§The AEGIS Collaboration consists of all listed authors except D.O.; there are no additional authors or collaborators.

theoretical considerations, such as conservation of energy combined with the observed blue-shift of light in gravitational fields (5); and by indirect experimental evidence, such as the lack of anomalous regeneration of K -short kaons (6), the precise measurement of the antiproton cyclotron frequency (7), and the times of arrival of neutrinos and antineutrinos from the supernova SN1987a (8). However, such arguments are not conclusive (9) and a direct experimental confirmation was lacking until recently.

Over the past decade, several experimental collaborations have been established with the goal of measuring the acceleration of antimatter in Earth's gravitational field, with most of these efforts taking place at the antimatter factory at CERN. These have culminated in an experiment by the ALPHA-g collaboration (10), which has measured the gravitational acceleration of antihydrogen ($\bar{H}$) to be $g_{\bar{H}} = (0.75 \pm 0.13_{\text{stat+sys}} \pm 0.16_{\text{sim}}) g$ where g is the local gravitational acceleration on ordinary matter. Zero gravitational pull ($g_{\bar{H}} = 0$) is disfavored compared to ordinary gravity ($g_{\bar{H}} = g$) with a Bayes factor of 2.9×10^{-4} , while antigravity ($g_{\bar{H}} = -g$) is conclusively ruled out.

The next steps in advancing the field involve replicating the measurement and then increasing the accuracy to subject the WEP to more stringent tests. Theoretical models that presuppose that antimatter and energy respond differently to gravitational fields (11, 12) result in potential deviations from the WEP at the percent level for hadronic matter, including antiprotons and antihydrogen. According to the standard model, most of the mass of an antiproton, around $938 \text{ MeV}/c^2$, stems from its internal binding energy (13), whereas the masses of the three constituent antiquarks add up to around $9 \text{ MeV}/c^2$ (14). Since it is established that binding energy responds positively to gravity (1, 2), the deviation $\Delta g = g_{\bar{H}} - g$ would not be expected to exceed 1% (15, 16).

Achieving a 1% precision on $g_{\bar{H}}$ is a challenging but realistic goal pursued by the competing experiments ALPHA-g (17), GBAR (18), and AEGIS (19) at CERN. These use substantially different methods to measure the effect of gravity on antihydrogen, each one requiring the development of bespoke technologies and the solution of distinctive technological challenges. The gravitational measurement at AEGIS is based on a moiré deflectometer [already tested with antiprotons (20)] in which the particles pass through two material grids before annihilating onto a position-sensitive detector. The vertical deflection of the moiré pattern, given by $\delta y = -t^2 g_{\bar{H}}$ for a time of flight t between the grids, is expected to be tens of micrometers for the cold antihydrogen beam of AEGIS. Therefore, a crucial requirement for high-precision gravity measurements at AEGIS is the real-time detection of the position of $\bar{H}$ annihilations with micrometric accuracy. Previously considered detection technologies included nuclear photographic emulsions (21–23) and bespoke silicon detectors (24), such as Timepix3 (25, 26). Nuclear emulsions feature a high resolution, approaching $1 \mu\text{m}$ (21), but, due to the lack of real-time detection, it is challenging to perform on-line monitoring of the position of the photographic plate relative to the grids. On the other hand, real-time detection is possible with silicon detectors, but the ones so far available had a substantially lower resolution. For instance, the pixels of Timepix3 and of Timepix4 are $55 \mu\text{m}$ by $55 \mu\text{m}$ in size (27, 28).

In this work, we introduce a groundbreaking $\bar{H}$ detection technology which, for the first time, meets all the requirements to reach

a 1% precision measurement of $g_{\bar{H}}$ at AEGIS. This is based on the Sony IMX219, a commercial complementary metal-oxide semiconductor (CMOS) optical image sensor with 8 megapixels and a 3.67 mm by 2.76 mm sensitive area (29, 30), originally developed for mobile applications and which has already been shown to be capable of imaging low-energy positrons with exceptional efficiency and resolution (31), with a cost that is three orders of magnitude lower than that of bespoke detectors such as Timepix3. Its $1.12 \mu\text{m}$ by $1.12 \mu\text{m}$ pixels are 50 times smaller than that of Timepix3 and of size similar to that of nuclear emulsions grains. We have now experimentally observed that the annihilation of antiprotons ($\bar{p}$) on the surface of the CMOS sensor results in the secondary charged particles leaving detectable signals in the exposed images. By reconstructing the vertex lying at the intersection of the tracks, the position of the antiproton annihilation can be determined with submicrometer accuracy. Since antihydrogen is an antiproton having only an extra positron bound to it, our detector is expected to be an antihydrogen annihilation vertexer as well and thus enable $\bar{H}$ gravity measurements.

RESULTS Detection

Low-energy antiprotons impinging on matter are trapped, through the Day-Snow-Sucher mechanism (32), by atomic nuclei and then quickly annihilate with either a proton or a neutron, releasing almost 1.9 GeV of energy. Through the interaction of the constituents quarks $p\bar{p}$ and $n\bar{p}$ annihilations result in the emission of two to eight pions (π^- , π^0 , π^+) and other particles (33, 34). The annihilation in heavy nuclei can result in the recoil of some of the adjacent protons and neutrons and each of these, if the trajectory crosses the nucleus, can also pick up other nucleons and result in the emission of deuterons, tritium, helium, and other heavier nuclear fragments (33, 35). The secondary particle branching ratios and spectra had been experimentally characterized at the Low Energy Anti-Proton Ring facility between 1982 and 1996 (36–41).

We have detected $\bar{p}$ annihilation events by repeatedly exposing the CMOS sensor to a low-intensity beam of antiprotons. Over the course of 8 days a total of 1576 images were exposed to collect antiproton events. Each shot was preceded by an exposure without antiprotons for background subtraction. Within the recorded images a total of 2601 $\bar{p}$ annihilation events were manually identified. Annihilations appear as star-shaped events with multiple prongs emanating from one single primary vertex (see Fig. 1).

The sensor was prepared by removal of the microlenses and Bayer filter using the procedure described in (31), but leaving the passivation and wire grid layers in place. At the used implantation energy of 8 keV , most of the antiprotons annihilate within $0.25 \mu\text{m}$ from the surface, directly above the sensor's sensitive volume, which is thus intersected by half of the emitted secondary particles. Some of these are energetic charged particles that generate electron-hole pairs in the silicon, a process that results in a signal similar to the one produced by visible light which the detector integrated electronics is designed to pick up (29–31). Neutrons, neutral pions, photons, and Auger electrons are also featured prominently among the annihilation products, but are not expected to produce a noteworthy signal. Tertiary particles, e.g., due to in-flight decay of a secondary, are rarely observed.

Prong identification and detection efficiency

The vast majority of the recorded prongs are either straight lines (tracks) and elliptical-shaped prongs (ellipses). We have manually flagged the number and location of every track and ellipse within the dataset. We have run a least-square fit algorithm to precisely determine the average thickness in pixels of all tracks in the dataset (see the “Track fitting algorithms” section). The distribution in thickness of tracks is bimodal (see Fig. 2, top). By applying a threshold at 1.0 px of thickness, we can classify all prongs as either thick tracks (2382 instances, 29.9% of recorded prongs), thin tracks (3929 instances, 49.2% of recorded prongs), or ellipses (1666 instances, 20.9% of recorded prongs). Table 1 details the composition of recorded events.

We have experimentally characterized the response of the CMOS sensor to specific charged particles to assess the most likely associations between secondaries and the observed prongs. We have exposed the sensor to the decay products of an ^{241}Am source positioned at a 20° angle with respect to the surface and observed that the tracks left by the 5.4-MeV alpha particles appear as elliptical-shaped prongs with a consistent size of 4 px by 12 px. We have also exposed the sensor to a proton beam of 4 MeV of energy impinging at 10° angle with respect to the surface and observed them to produce linear tracks of consistent thickness in the images. We applied the same algorithm as described in the “Track fitting algorithms” section to determine the thickness of the proton tracks and found them to have thickness comprised between 1.0 and 1.5px (see Fig. 2, bottom).

On the basis of these observation, we attribute thick tracks to protons, thin tracks to charged pions, and the ellipses to deuterons, tritium, alpha particles, or heavier fragments. This assignment is supported by the fact that similar features can be observed in both

experimental and simulated $\bar{p}$ annihilation events on the Timepix3 (26). Furthermore, these three species are known to produce similar formations within cloud chambers (42), albeit three orders of magnitude larger in size as the density inside of a cloud chamber is about a thousand times lower than that of crystalline silicon.

We have further validated this prong identification by comparing experimental and simulated data. We have tallied the observed multiplicities per vertexed annihilation event, as reported in the last row of Table 2. We have then used FLUKA (43), which includes a state-of-the-art model of antiproton annihilation, to simulate $\bar{p}$ -Si annihilations and count the multiplicities of secondary particles that are emitted toward the half-space containing the sensor active volume. This results in the “FLUKA base prediction” in Table 2, which, however, significantly deviates from the experimental data. This is due to selection bias, since not all annihilation events can be vertexed, and to missed prong identifications, e.g., when a track is too short or due to occlusion from other prongs. To account for these effects, we have generated a synthetic dataset using 1000 FLUKA-generated events. For each event, a collection of tracks and ellipses is printed, according to the species of the secondary particles and their emission direction. We have manually flagged the events as traceable or untraceable and, for the latter, counted the number of tracks and ellipses that could be recognized. This results in the “FLUKA occlusion corrected” prediction, which shows a reasonable agreement with the observed data. Furthermore, by counting the traceable events, we estimate the vertex reconstruction efficiency to be around 70%.

Annihilation vertex reconstruction

We have attempted algorithmic fitting of the annihilation events, as previously done for Timepix3-based detections (26). We have




Fig. 1. Curated selection of antiproton annihilation events as imaged by the CMOS sensor. The observed shapes are similar to those recorded by the Timepix3 detector (25, 26), albeit at a scale approximately 50 times smaller. Pixels marked in magenta have been deemed non-functional by taking background images. Green arrows indicate examples of ellipse-shaped prongs, cyan arrows indicate examples of thick tracks, and orange arrows examples of thin tracks.




Fig. 2. Distribution of the widths of recorded tracks. In blue the distribution in thickness of the tracks in recorded antiprotons events. We attribute the higher-thickness peak of the distribution to tracks left in the sensor by protons and the lower peak to tracks left by pions. In red the distribution in thickness of tracks left by 4-MeV protons within the detector, matching the topmost part of the distribution in thickness of proton tracks. We attribute the difference between the distributions mainly to the difference in energy spectrum of the protons.

developed a model that predicts the intensity recorded by each pixel in the event based on a parameterization of the event (position of the vertex, number, and positions of the prongs); the fitting algorithm then finds the parameterization that minimizes the ℓ^2 -distance between the recorded data and the prediction. Despite promising initial results from this approach (reaching approximately 2.5 μm resolution), we found out that humans actually achieve higher accuracy. While modern machine learning algorithms can potentially match or surpass this accuracy, their training requires accurately labeled data in amounts far exceeding both the events gathered so far and those we can expect to collect in AEGIS in the near future.

Eight researchers within our team have independently determined the position of the annihilation vertex in each of the 2601 recorded events, task that has required each person between 5 and 10 hours of manual labeling work. The reconstructed positions are shown in Fig. 3C. The volunteers were provided with a graphical interface that prompted them with a 128 px by 128 px portion of the image containing an annihilation event. The interface allows marking the vertex position with a precision of 1/4 of a pixel and a tool to trace straight lines from the vertex outward, easing the evaluation of the alignment of the vertex position with the tracks in the event. Reconstructions of a vertex position made by different volunteers for the same event differ typically by less than one pixel, with a SD of 0.9 px in both the x and y direction. We have averaged the output of the volunteers to determine a best estimation of the vertex position.

Table 1. Number of recorded events sorted by prong composition. Prongs appearing as ellipses are identified as alpha particles or other multinucleon fragments (α), thick tracks are identified as protons (p) and thin tracks are identified as charged pions (π). Annihilation events featuring zero or one prongs cannot be traced and are excluded from the analysis (—). Most common are events featuring two prongs (679 counts), three prongs (812 counts), and four prongs (573 counts). This prong distribution is compatible with the one observed in previous experiments and with FLUKA simulations, once the selection bias has been accounted for (see Table 2).

α	π	0	1	2	3	4	5	6
	P							
0	0	—	—	71	34	9	1	0
	1	—	116	149	61	24	5	2
	2	81	107	108	64	17	5	0
	3	33	51	59	31	11	5	1
	4	4	16	12	9	2	3	0
	5	0	0	1	1	1	1	0
	6	0	0	0	0	1	0	0
1	0	—	101	44	17	5	0	0
	1	289	247	88	23	5	0	0
	2	156	153	67	13	6	0	0
	3	29	43	30	11	5	1	0
	4	6	4	3	1	3	0	0
	5	0	0	1	0	0	0	0
2	0	21	14	5	1	0	0	0
	1	23	30	6	6	2	0	0
	2	17	10	5	1	0	0	1
	3	1	2	2	0	0	0	0
3	0	5	0	0	0	0	0	0
	1	0	1	0	0	0	0	0
	2	0	0	1	0	0	0	0

Table 2. Prongs multiplicities as observed in the experimental dataset and in FLUKA-based predictions. For simulated data, it is assumed that charged pions result in thin tracks, protons in thick tracks, all fragments containing two or more nucleons result in ellipses, while all other particles are ignored. The base FLUKA predictions have to be corrected for selection bias in the vertexing procedure and for occlusions among prongs, see main text for details.

Prong type	Ellipse (α)	Thick track (p)	Thin track (π)
Particle identification	Alpha/fragment	Proton	Charged pion
FLUKA base prediction	1.91	0.85	1.37
FLUKA occlusion corrected	0.75	0.90	1.46
Selection criteria	Hand tagging	Width ≥ 1.0 px	Width < 1.0 px
Experimental data	0.64	0.91	1.50

As long as no significant systematic bias is present, the accuracy of the average position should scale as $0.9/\sqrt{n}$ px, where n is the number of independent vertex reconstructions. For $n = 8$, this would theoretically result in a resolution of 0.32 px (0.36 μm).

Grid positioning and vertexing accuracy

We have performed a bias-free assessment of the crowd-based vertexing accuracy via a procedure akin to a optical transfer function measurement, a method used to determine the resolution of digital camera sensors (44). Namely, we have occluded part of the sensor so that it cannot be reached by the impinging antiprotons and observed the sharpness of the transition in the density of annihilation events between occluded and nonoccluded portions of the sensor. We have placed a silicon nitride grid of thickness 125 μm consisting of teeth with a pitch of 100 μm and openings of 40 μm directly onto the sensor surface. To cover most of the active surface of the sensor while not interfering with the bonding wires, the grid was cut to size using a hardened steel scribe and then glued in place with thermoplastic adhesive.

The grid was brought as close as possible to the sensor by observing the grid shadow as imaged by the device in real time using visible light and using the sharpness of its shadow to assess its proximity to the surface. An image of the grid, obtained from the sensor itself after it was installed in vacuum is shown in Fig. 3B). In the image, two of the grid teeth are bent upward, which was not the case before air was pumped out of the chamber. Most likely, this is due to mechanical stress caused by air pockets deforming the adhesive when vacuum was applied and had to be factored in during the data analysis.

The position of the grid relative to the sensor was measured between each run by using the residual light given off by a Pirani gauge, which was then switched off to allow the sensor to operate in darkness. We determined the position of each tooth of the grid with sub-pixel accuracy by using the algorithm described in the “Grid fitting algorithms” section. By fitting multiple images acquired in quick succession over the course of 1 hour (see Fig. 4, left), we found the algorithm to be stable, with a SD of the results below 0.12 μm . Tracking of the grid position over the course of the measurement campaign reveals a linear drift in the order of 0.1 μm per day (see Fig. 4, right). This effect is most likely due to the combination of the mechanical tension introduced in the adhesive during evacuation and the adhesive softening under the heat load of the detector during operation, which reaches temperatures in excess of 60°C. To account for this drift, the position of the grid at any given time was interpolated using a linear regression model. This technique allowed in situ

calibration of the grid position, ensuring consistency throughout the measurement campaign.

Antiprotons annihilating onto the grid also sometimes produce tracks, but these have a different appearance from the events shown in Fig. 1, allowing their exclusion of these events from the analysis. In these cases, the annihilations are offset by 125 μm from the surface of the sensor, resulting in disjoint tracks that do not touch at a vertex. For each crowd-reconstructed vertex, the signed distance d to the closest tooth edge was computed and the vertices having $|d| \leq 25 \mu\text{m}$ were collected. The resulting distribution (in Fig. 3D) resembles, as expected, an error-function distribution (44) and is modeled as $f(d) = b + n \operatorname{erf}\left[d/\left(\sqrt{2}r\right)\right]$ with fit parameters b, n , and r , where r represents a upper bound of the resolution that is achievable with the sensor. Via a maximum likelihood fit, we obtain $r = 0.62^{+0.40}_{-0.22} \mu\text{m}$ for crowd-based vertexing, while $r = 0.79^{+0.35}_{-0.24} \mu\text{m}$ is consistently obtained when the vertexing from a single volunteer is used.

Sensor resilience

As the measurement was carried out, the emergence of dead pixels has been observed. Malfunctioning pixels in the detector manifest characteristically as pixels whose measurement baseline is uncharacteristically high, typically exceeding one fourth of the total dynamic range and often saturating it completely. These pixels can be easily identified in the background images taken before each antiproton implantation. The pristine sensor contained about 2500 dead pixels (one in 3200), defined as pixels whose baseline exceeded 400 lsb (least significant bits), when acquiring in complete darkness with the same settings used to detect antiprotons, with the maximum possible readout being 1023 lsb.

As we implant antiprotons in the device, we observe pixels which get permanently damaged by the radiation impinging on the detector. Because of the limitations of the beam optics during this run, most of the energy deposited in the sensor during our measurements did not come from antiprotons annihilating on the detector, but instead from antiprotons annihilating elsewhere in the chamber whose annihilation products traversed the active volume of the sensor.

We evaluated their contribution to the total irradiation of the sensor by integrating the signal that they produced in the sensor and then dividing it by the average signal induced by an antiproton (38k lsb). Using this conversion we observed the appearance of one additional permanently damaged pixel every four equivalent antiprotons implanted into the sensor. This rate of degradation is




Fig. 3. Reference grid used to determine the sensor resolution. (A) Optical image of the silicon nitride grid acquired using a point light source before installing the setup in vacuum. (B) A similar image obtained by exploiting the light emitted by a vacuum gauge in the apparatus. Arrows indicate the two grid teeth that were bent by the adhesive deforming under vacuum. (C) The reconstructed position of antiproton annihilations recorded with the grid installed onto the sensor. Toward the left side two distinct areas, nearly devoid of annihilations events can be seen. These are the regions where the thermoplastic adhesive keeping the grid in place was applied. (D) A histogram of the distance of the annihilations events from the nearest edge. Overlaid in orange is the best fitting error function found via maximum likelihood.




Fig. 4. Precision and accuracy of the grid fitting method. (Left) Relative drift of the endpoints of the 50 grid teeth as determined by the fitting algorithm described in the “Grid fitting algorithms” section over the course of 1 hour. One of the edges has been highlighted in red to better show the typical progression of the algorithm output over time. The fluctuations in the so reconstructed coordinates are below 0.12- μm root mean square (RMS) for all the grid vertices, with median being 0.031- μm RMS. (Right) Relative position of one grid vertex tracked over the course of the 8-day measurement campaign. The linear fit used to compensate for the grid movement in the data analysis is shown in orange.

completely negligible for its use in AEgIS where an integrated flux of a few thousand antihydrogen atoms is expected during the course of the entire experiment. The detector can be foreseen to be suitable to support experiments requiring an antiproton/antihydrogen flux between two and three order of magnitude larger.

DISCUSSION

We have demonstrated the possibility of detecting antiproton annihilations using a commercial mobile camera sensor. We have shown that, using crowd-sourced vertex reconstruction, a position accuracy of $0.62^{+0.40}_{-0.22}$ μm can be achieved, a 35-fold improvement over the previous state of the art of 22 μm for real-time detection (26). Making use of FLUKA simulations, we can estimate that around 70% of the annihilating antiprotons result in traceable events. Differently from previous use of the same detector for positrons (31), most of the energy deposited in the sensor by antiprotons comes from the rest mass of the annihilating particles. As such, we expect no lower limit in the antiparticle kinetic energy to vertex the annihilation event and, thus, this sensor could be directly used to detect cold antihydrogen in AEgIS gravity measurement.

The sensor is by design sensitive to visible light, which enables the accurate determination of its position relative to the moiré deflectometer grids by means of optical alignment. In essence, photons can serve as test particles in a gravitational experiment: Being their deflection by Earth's gravitational field negligible, they can be used to ascertain the expected arrival point of particles in the absence of gravitational acceleration. Electrons with kiloelectronvolt-scale energy might also be used in alternative to photons. Thus, by alternating between optical calibrations and antihydrogen shots a direct differential measurement of particle arrival positions at the detector can be performed. The use of a single device both for optical imaging and for antimatter detection ensures that all measurements occur within the same physical frame of reference, minimizing systematic errors. Furthermore, any drift in the position of the deflectometer grids can be detected and accounted for, as demonstrated in this work.

Following the measurements results presented here, this sensor technology has been selected as the basis for the development of a bespoke detector to be employed within the AEgIS deflectometer. The detector will feature a large sensitive area (around 5.8 cm by 5.7 cm), consisting of 48 individual CMOS sensors arranged in a compact rectangular tessellation, which is expected to collect 56% of the antihydrogen atoms that pass through the deflectometer grids. The submicrometric accuracy and the in situ calibration capabilities of this detector technology should allow measuring the gravitational acceleration to 1% precision, which is the AEgIS scientific goal, under relaxed experimental constraints.

Ultimately, we expect that this detector technology could enable in future upgrades to considerably exceed the 1% precision goal in the measurement of g_H . As a final outlook, this sensor technology shows great promise for a broad range of applications, beyond the detection of antiprotons, due to its sensitivity to both energetic charged particles and light. We have already demonstrated that it can detect positrons (31) and extreme-ultraviolet (XUV) light (publication upcoming), and we expect that it may be used in biomedical imaging (45), in visible and XUV light spectrometry, as well as in high-resolution particle tracking.

METHODS

Hardware setup

The apparatus used in (31), seen there in Fig. 1B, was repurposed for this experiment. The flange there depicted was installed horizontally onto a 45° offshoot of the injection line of AEgIS, facing in the direction of the 5-T magnet of the experiment (see Fig. 5). Between the detector and the injection line, a 10.4-m-long, 4-m-wide restriction terminating in a 2-m-wide aperture on the side of the detector was installed, while on the side of the injection line, a pneumatically actuated gate valve was placed. The portion of tube containing the detector and the restriction were both evacuated using separate turbo pumps, reaching a vacuum of 2×10^{-7} mbar. The gate valve was opened only briefly during the injection of the antiprotons, to limit the contamination of the AEgIS vacuum from the sensor readout system, which was not designed to reach higher levels of vacuum.

Antiprotons were captured from the Extra Low Energy Antiproton ring (ELENA) by the main AEgIS apparatus and then dumped back into the injection line using a purposely implemented procedure in the experiment control system (46). The injection line has been instrumented with two pairs of einzel lenses and a pair of deflecting electrodes, to allow the formation of a beam of antiprotons in two offshoot lines onto one of which the detector apparatus was installed. Unfortunately, many of the electrodes were not available during the course of this experiment, so only minimal focusing of the re-emitted antiprotons was possible. This was not an issue, as the high number of antiprotons available from AEgIS (estimated 4×10^6) allowed to record on average 1.9 events on the detector in each run, thus allowing for the execution of the experiment.

As in (31), images from the sensor were transmitted outside the vacuum chamber through a WiFi bridge. Synchronization of the valve actuation and minimization of its opening time was achieved acoustically by installing a microphone onto the valve and matching the recorded audio to the master clock of the experiment.

Track fitting algorithms

The algorithm processes a 128 pixel by 128 pixel section of the image that includes a preselected annihilation event and outputs the widths of all present tracks. Since tracks and ellipses in each annihilation event often overlap, it is essential to estimate their widths jointly to minimize biases. As auxiliary input, the number of tracks and ellipses that are present in the image has to be provided, as well as a preliminary estimation of positions of these tracks and ellipses. Each track position is identified by its two endpoints, $\vec{p}_0 = (x_0, y_0)$ and $\vec{p}_1 = (x_1, y_1)$, while each ellipse is identified by its center $\vec{p}_c = (x_c, y_c)$ and by two distinct points on its boundary, $\vec{p}_a = (x_a, y_a)$ and $\vec{p}_b = (x_b, y_b)$, so that the boundary can be parameterized as $\vec{p}(\phi) = (\vec{p}_a - \vec{p}_c)\sin(\phi) + (\vec{p}_b - \vec{p}_c)\cos(\phi)$, for $\phi \in [0, 2\pi]$. The initial positions are a human inputs and must be accurate within 2 pixels.

The widths of the tracks are estimated by modeling the expected appearance of the annihilation event based on a few underlying parameters and then identifying the parameters that best fit the observed data. Specifically, an annihilation event containing n_{ell} ellipses and n_{tr} tracks is described via the parameter set $\mathcal{T} = \{(\vec{p}_{a,i}, \vec{p}_{b,i}, \vec{p}_{c,i})\}_{i=1}^{n_{\text{ell}}} \cup \{(\vec{p}_{0,i}, \vec{p}_{1,i}, w_i)\}_{i=1}^{n_{\text{tr}}}$, where $w_i > 0$ is the width of the i track.




Fig. 5. Detail of the beamline of AEGLS, showing the injection line from ELENA and part of the trap complex installed inside the 5-T trap. Individual antiproton bunches from ELENA pass through a degrader and are caught by the AEGLS C trap (red arrows). Electrode voltages in the beamline are then reconfigured to allow extraction toward the 45° offshoot, after which the trap is opened and the antiprotons implanted into the sensor (green arrows).

Given the parameterization $\mathcal{T}$ of an event, a model of the intensities of the pixels is obtained as follows. The intensity $I(\vec{r})$ of the pixel with coordinates $\vec{r} = (x, y)$, assumed to be at the center of the pixel, ranges from 0 (black) to 1 (white). The distance d of each pixel to the boundary of each ellipse is numerically computed, with $d > 0$ ($d < 0$) indicating points inside (outside) an ellipse. The pixel intensities due the i -th ellipse are

$$I_i^{\text{ell}}(\vec{r}) = \begin{cases} 1 & \text{if } d < 0 \\ 1 - d & \text{if } 0 \leq d < 1 \\ 0 & \text{if } d \geq 1. \end{cases} \quad (1)$$

Similarly, the distance d of each pixel to each track is also numerically computed (being a track identified by a segment, this distance cannot be negative). The pixel intensities due the i -th track are

$$I_i^{\text{tr}}(\vec{r}) = \begin{cases} 1 & \text{if } d < w_i \\ 1 - d & \text{if } w_i \leq d < w_i + 1 \\ 0 & \text{if } d \geq w_i + 1. \end{cases} \quad (2)$$

This differs from anti-aliasing algorithms for drawing lines in computer graphics, but it more closely resembles the detector physics and provides a better fit to the tracks. Last, the intensity of each pixel in the model is obtained by summing the individual contributions and clipping the result to one, i.e., $I_{\mathcal{T}}(\vec{r}) = \min[1, \sum_{i=1}^{n_{\text{ell}}} I_i^{\text{ell}}(\vec{r}) + \sum_{i=1}^{n_{\text{tr}}} I_i^{\text{tr}}(\vec{r})]$.

The ℓ^2 distance between the modeled intensities $I_{\mathcal{T}}$ and the observed intensities I_{data} is computed as

$$\ell^2(\mathcal{T}) = \sum_{\vec{r} \in \mathcal{R}} |I_{\mathcal{T}}(\vec{r}) - I_{\text{data}}(\vec{r})|^2 \quad (3)$$

where the dead pixels are excluded from the summation domain $\mathcal{R}$. The parameters in $\mathcal{T}$ are then varied within 2 pixels from their preset values and a local minimum of $\ell^2(\mathcal{T})$ is obtained via a Nelder-Mead optimizer. From our analyses, we expect these local minima to be also global ones. The values of the track thicknesses are extracted from the value of $\mathcal{T}$ found by the optimizer.

Grid fitting algorithms

Given as input an image taken by the sensor and set of segments providing a preliminary estimation of the positions of the edges of the teeth, the algorithm outputs a refined estimation of the position of these edges. The preliminary position estimation is a human input.

Let k be the number of tooth edges (typically, twice the number of teeth) and for each $i \in \{1, \dots, k\}$, let the points $(x_{0,i}, y_{0,i})$, $(x_{1,i}, y_{1,i})$ be the end points of a segment indicating approximately the position of the i -th edge. It is assumed that the segment is almost horizontal (i.e., $|x_{1,i} - x_{0,i}| \gg |y_{1,i} - y_{0,i}|$) and, without loss of generality, that $x_{1,i} > x_{0,i}$. The equation of the i -th segment is

$$y_i(x) = \frac{y_{1,i} - y_{0,i}}{x_{1,i} - x_{0,i}}x + \frac{x_{1,i}y_{0,i} - x_{0,i}y_{1,i}}{x_{1,i} - x_{0,i}} \text{ for } x_{0,i} \leq x \leq x_{1,i} \quad (4)$$

A band of pixels having width $2w$ around each segment is considered, given by the pixels having coordinates (x, y) within vertical distance w from the i -th segment. Let their intensities in the image be $I_i(x, y)$. We define $\bar{I}_i(x, y)$ as a Gaussian smoothing of these intensities along the vertical direction within a band, i.e.,

$$\bar{I}_i(x, y) = \frac{\sum_{y' \in B_i(x)} I_i(x, y') e^{-\frac{(y-y')^2}{s^2}}}{\sum_{y' \in B_i(x)} e^{-\frac{(y-y')^2}{s^2}}} \quad B_i(x) = \{y: |y - y_i(x)| \leq w\} \quad (5)$$

Let p be a real indicating the portion of image covered by the grid and $N(I)$ the number of pixels having intensity smaller or equal than I , with $N(\infty)$ denoting the total number of pixels in the image. First, a threshold value I_p is determined as the largest intensity such that $N(I_p) < p \cdot N(\infty)$. Then, the equation

$$\bar{I}_i(x_i, y) = I_p \quad (6)$$

is solved numerically in y for all $i \in \{1, \dots, k\}$ and for all $x_i \in \{x_{0,i}, \dots, x_{1,i}\}$. If the solution to Eq. 6 is not unique, the point is discarded and a warning is raised. For each edge i , a collection of points $C_i = \{(x_i, y_i): \bar{I}_i(x_i, y_i) = I_p \text{ and } y_i \text{ is unique}\}$ is created. Last, for each edge i , the output is a straight line obtained via linear regression of y as a function of x over the collection C_i .

In our case, the tunable parameters of the algorithm were set to $p = 0.6$, $w = 10$, and $s^2 = 3$.

REFERENCES AND NOTES

- T. A. Wagner, S. Schlamminger, J. H. Gundlach, E. G. Adelberger, Torsion-balance tests of the weak equivalence principle. *Class. Quantum Gravity* **29**, 184002 (2012).
- P. Touboul, G. Métris, M. Rodrigues, J. Bergé, A. Robert, Q. Baghi, Y. André, J. Bedouet, D. Boulanger, S. Bremer, P. Carle, R. Chhun, B. Christophe, V. Cipolla, T. Damour, P. Danto, L. Demange, H. Dittus, O. Dhuicque, P. Fayet, B. Foulon, P.-Y. Guidotti, D. Hagedorn, E. Hardy, P.-A. Huynh, P. Kayser, S. Lala, C. Lämmerzahl, V. Lebat, F. Liorzou, M. List, F. Löffler, I. Panet, M. Pernot-Borràs, L. Perraud, S. Pires, B. Pouilloux, P. Prieur, A. Rebray, S. Reynaud, B. Rievers, H. Selig, L. Serron, T. Sumner, N. Tanguy, P. Torresi, P. Visser, MICROSCOPE Collaboration, MICROSCOPE mission: Final results of the test of the equivalence principle. *Phys. Rev. Lett.* **129**, 121102 (2022).
- F. C. Witteborn, W. M. Fairbank, Experiments to determine the force of gravity on single electrons and positrons. *Nature* **220**, 436–440 (1968).
- M. H. Holzschneider, R. E. Brown, J. B. Camp, S. Cornford, T. Darling, P. Dyer, T. Goldman, S. Høibråten, K. Hosea, R. J. Hughes, N. Jarmie, R. A. Kenefick, N. S. P. King, D. C. Lizon, M. M. Nieto, M. M. Midzor, S. P. Parry, J. Rochet, R. A. Ristinen, M. M. Schauer, J. A. Schecker, F. C. Witteborn, Trapping of antiprotons in a large penning trap – Progress towards a measurement of the gravitational acceleration of the antiproton. *Nucl. Phys. A* **558**, 709–718 (1993).
- P. Morrison, Approximate nature of physical symmetries. *Am. J. Phys.* **26**, 358–368 (1958).
- M. L. Good, K_2^0 and the equivalence principle. *Phys. Rev.* **121**, 311–313 (1961).
- M. J. Borcher, J. A. Devlin, S. R. Erlewein, M. Fleck, J. A. Harrington, T. Higuchi, B. M. Latacz, F. Voelken, E. J. Wursten, F. Abbass, M. A. Bohman, A. H. Mooser, D. Popper, M. Wiesinger, C. Will, K. Blaum, Y. Matsuda, C. Ospelkaus, W. Quint, J. Walz, Y. Yamazaki, C. Smorra, S. Ulmer, A 16-parts-per-trillion measurement of the antiproton-to-proton charge–mass ratio. *Nature* **601**, 53–57 (2022).
- J. M. LoSecco, Limits on cp invariance in general relativity. *Phys. Rev. D Part. Fields* **38**, 3313–3313 (1988).
- M. M. Nieto, T. Goldman, The arguments against “antigravity” and the gravitational acceleration of antimatter. *Phys. Rep.* **205**, 221–281 (1991).
- E. K. Anderson, C. J. Baker, W. Bertsche, N. M. Bhatt, G. Bonomi, A. Capra, I. Carli, C. L. Cesar, M. Charlton, A. Christensen, R. Collister, A. C. Mathad, D. D. Quiceno, S. Eriksson, A. Evans, N. Evetts, S. Fabbri, J. Fajans, A. Ferwerda, T. Friesen, M. C. Fujiwara, D. R. Gill, L. M. Golino, M. B. G. Gonçalves, P. Grandemange, P. Granum, J. S. Hangst, M. E. Hayden, D. Hodgkinson, E. D. Hunter, C. A. Isaac, A. J. U. Jimenez, M. A. Johnson, J. M. Jones, S. A. Jones, S. Jonsell, A. Khramov, N. Madsen, L. Martin, N. Massacret, D. Maxwell, J. T. K. M. Kenna, S. Menary, T. Momose, M. Mostamand, P. S. Mullán, J. Nauta, K. Olchanski, A. N. Oliveira, J. Peszka, A. Powell, C. Ø. Rasmussen, F. Robicheaux, R. L. Sacramento, M. Sameed, E. Sarid, J. Schoonwater, D. M. Silveira, J. Singh, G. Smith, C. So, S. Stracka, G. Stutter, T. D. Tharp, K. A. Thompson, R. I. Thompson, E. Thorpe-Woods, C. Torkzaban, M. Urioni, P. Woosaree, J. S. Wurtele, Observation of the effect of gravity on the motion of antimatter. *Nature* **621**, 716–722 (2023).
- H. Bondi, Negative mass in general relativity. *Rev. Mod. Phys.* **29**, 423–428 (1957).
- L. I. Schiff, Gravitational properties of antimatter. *Proc. Natl. Acad. Sci. U.S.A.* **45**, 69–80 (1959).
- F. Wilczek, Origins of mass. *Centr. Eur. J. Phys.* **10**, 1021–1037 (2012).
- Particle Data Group, R. L. Workman, V. D. Burkert, V. Crede, E. Klempf, U. Thoma, L. Tiator, K. Agashe, G. Aielli, B. C. Allanach, C. Amsler, M. Antonelli, E. C. Aschenauer, D. M. Asner, H. Baer, S. Banerjee, R. M. Barnett, L. Baudis, C. W. Bauer, J. J. Beatty, V. I. Belousov, J. Beringer, A. Bettini, O. Biebel, K. M. Black, E. Blucher, R. Bonventre, V. V. Bryzgalov, O. Buchmüller, M. A. Bychkov, R. N. Cahn, M. Carena, A. Ceccucci, A. Cerri, R. S. Chivukula, G. Cowan, K. Cranmer, O. Cremonesi, G. D’Ambrosio, T. Damour, D. de Florian, A. de Gouvêa, T. De Grand, P. de Jong, S. Demers, B. A. Dobrescu, M. D’Onofrio, M. Doser, H. K. Dreiner, P. Eerola, U. Egede, S. Eidelman, A. X. El-Khadra, J. Ellis, S. C. Eno, J. Erler, V. V. Ezhela, W. Fetscher, B. D. Fields, A. Freitas, H. Gallagher, Y. Gershtein, T. Gherghetta, M. C. Gonzalez-Garcia, M. Goodman, C. Grab, A. V. Gritsan, C. Grojean, D. E. Groom, M. Grünewald, A. Gurtu, T. Gutsche, H. E. Haber, M. Hamel, C. Hanhart, S. Hashimoto, Y. Hayato, A. Hebecker, S. Heinemeyer, J. J. Hernández-Rey, K. Hikasa, J. Hisano, A. Höcker, J. Holder, L. Hsu, J. Huston, T. Hyodo, A. Ianni, M. Kado, M. Karliner, U. F. Katz, M. Kenzie, V. A. Khoze, S. R. Klein, F. Krauss, M. Kreps, P. Krizan, B. Krusche, Y. Kwon, O. Lahav, J. Laiho, L. P. Lellouch, J. Lesgourgues, A. R. Liddle, Z. Ligeti, C.-J. Lin, C. Lippmann, T. M. Liss, L. Littenberg, C. Lourenço, K. S. Lugovsky, S. B. Lugovsky, A. Lusiani, Y. Makida, F. Maltoni, T. Mannel, A. V. Manohar, W. J. Marciano, A. Masoni, J. Matthews, U.-G. Meißner, I.-A. Melzer-Pellmann, M. Mikhasenko, D. J. Miller, D. Milstead, R. E. Mitchell, K. Mönig, P. Molaro, F. Moortgat, M. Moskvic, K. Nakamura, M. Narain, P. Nason, S. Navas, A. Nelles, M. Neubert, P. Nevski, Y. Nir, K. A. Olive, C. Patrignani, J. A. Peacock, V. A. Petrov, E. Pianori, A. Pich, A. Piepke, F. Pietropaolo, A. Pomarol, S. Pordes, S. Profumo, A. Quadri, K. Rabbertz, J. Rademacker, G. Raffelt, M. Ramsey-Musolf, B. N. Ratcliff, P. Richardson, A. Ringwald, D. J. Robinson, S. Roesler, S. Rolli, A. Romaniouk, L. J. Rosenberg, J. L. Rosner, G. Rybka, M. G. Ryskin, R. A. Ryutin, Y. Sakai, S. Sarkar, F. Sauli, O. Schneider, S. Schönert, K. Scholberg, A. J. Schwartz, J. Schwiening, D. Scott, F. Sefkow, U. Seljak, V. Sharma, S. R. Sharpe, V. Shiltsev, G. Signorelli, M. Sileri, F. Simon, T. Sjöstrand, P. Skands, T. Skwarnicki, G. F. Smoot, A. Soffer, M. S. Sozzi, S. Spanier, C. Spiering, A. Stahl, S. L. Stone, Y. Sumino, M. J. Syphers, F. Takahashi, M. Tanabashi, J. Tanaka, M. Taševský, K. Terao, K. Terashi, J. Terning, R. S. Thorne, M. Titov, N. P. Tkachenko, D. R. Tovey, K. Trabelsi, P. Urquijo, G. Valencia, R. Van de Water, N. Varelas, G. Venanzoni, L. Verde, I. Vivarelli, P. Vogel, W. Vogelsang, V. Vorobyev, S. P. Wakely, W. Walkowiak, C. W. Walter, D. Wands, D. H. Weinberg, E. J. Weinberg, N. Wermes, M. White, L. R. Wiencke, S. Willocq, C. G. Wohl, C. L. Woody, W.-M. Yao, M. Yokoyama, R. Yoshida, G. Zanderighi, G. P. Zeller, O. V. Zenin, R.-Y. Zhu, S.-L. Zhu, F. Zimmermann, P. A. Zyla, Review of particle physics. *Prog. Theor. Exp. Phys.* **2022**, 083C01 (2022).
- M. Fischler, J. Lykken, T. Roberts. Direct observation limits on antimatter gravitation. arXiv:0808.3929 (2008).
- D. S. M. Alves, M. Jankowiak, P. Saraswat, Experimental constraints on the free fall acceleration of antimatter. arXiv:0907.4110 (2009).
- W. A. Bertsche, Prospects for comparison of matter and antimatter gravitation with alpha-g. *Philos. Trans. A Math. Phys. Eng. Sci.* **376**, 20170265 (2018).
- P. Pérez, D. Banerjee, F. Biraben, D. Brook-Berge, M. Charlton, P. Cladé, P. Comini, P. Crivelli, O. Dalkarov, P. Debu, A. Douillet, G. Dufour, P. Dupré, S. Eriksson, P. Froelich, P. Grandemange, S. Guellati, R. Guérou, J. M. Heinrich, P.-A. Hervieux, L. Hilico, A. Husson, P. Indelicato, S. Jonsell, J.-P. Karr, K. Khabarova, N. Kolachevsky, N. Kuroda, A. Lambrecht, A. M. M. Leite, L. Liskay, D. Lunney, N. Madsen, G. Manfredi, B. Mansoulié, Y. Matsuda, A. Mohri, T. Mortensen, Y. Nagashima, V. Nesvizhevsky, F. Nez, C. Regenfus, J.-M. Rey, J.-M. Reymond, S. Reynaud, A. Rubbia, Y. Sacquin, F. Schmidt-Kaler, N. Sillitoe, M. Staszczak, C. I. Szabo-Foster, H. Torii, B. Vallage, M. Valdes, D. P. Van der Werf, A. Voronin, J. Walz, S. Wolf, S. Wronka, Y. Yamazaki, The gbar antimatter gravity experiment. *Hyperfine Interact.* **233**, 21–27 (2015).
- A. Kellerbauer, M. Amoretti, A. S. Belov, G. Bonomi, I. Boscolo, R. S. Brusa, M. Büchner, V. M. Byakov, L. Cabaret, C. Canali, C. Carraro, F. Castelli, S. Cialdi, M. de Combarieu, D. Comparat, G. Consolati, N. Djourellov, M. Doser, G. Drobychev, A. Dupasquier, G. Ferrari, P. Forget, L. Formaro, A. Gervasini, M. G. Giammarchi, S. N. Gninenko, G. Gribakin, S. D. Hogan, M. Jacquy, V. Lagomarsino, G. Manuzio, S. Mariazzi, V. A. Matveev, J. O. Meier, F. Merkt, P. Nedelec, M. K. Oberthaler, P. Pari, M. Prevedelli, F. Quasso, A. Rotondi, D. Sillou, S. V. Stepanov, H. H. Stroke, G. Testera, G. M. Tino, G. Tréneç, A. Vairo, J. Vigué, H. Walters, U. Warring, S. Zavatarelli, D. S. Zvezhinskij, (AEGIS Proto-Collaboration), Proposed antimatter gravity measurement with an antihydrogen beam. *Nucl. Instrum. Methods Phys. Res. B* **266**, 351–356 (2008).
- S. Aghion, O. Ahlén, C. Amsler, A. Ariga, T. Ariga, A. S. Belov, K. Berggren, G. Bonomi, P. Bräunig, J. Bremer, R. S. Brusa, L. Cabaret, C. Canali, R. Caravita, F. Castelli, G. Cerchiari, S. Cialdi, D. Comparat, G. Consolati, H. Derking, S. Di Domizio, L. Di Noto, M. Doser, A. Dudarev, A. Ereditato, R. Ferragut, A. Fontana, P. Genova, M. Giammarchi, A. Gligorova, S. N. Gninenko, S. Haider, T. Huse, E. Jordan, L. V. Jørgensen, T. Kaltenbacher, J. Kawada, A. Kellerbauer, M. Kimura, A. Knecht, D. Krasnický, V. Lagomarsino, S. Lehner, A. Magnani, C. Malbrunot, S. Mariazzi, V. A. Matveev, F. Moia, G. Nebbia, P. Nédélec, M. K. Oberthaler, N. Pacifico, V. Petráček, C. Pistillo, F. Prelz, M. Prevedelli, C. Regenfus, C. Riccardi, O. Röhne, A. Rotondi, H. Sandaker, P. Scampoli, J. Storey, M. A. S. Vasquez, M. Špaček, G. Testera, R. Vaccarone, E. Widmann, S. Zavatarelli, J. Zmeskal, A moiré deflectometer for antimatter. *Nat. Commun.* **5**, 4538 (2014).
- M. Kimura, S. Aghion, O. Ahlén, C. Amsler, A. Ariga, T. Ariga, A. S. Belov, G. Bonomi, P. Bräunig, J. Bremer, R. S. Brusa, G. Burghart, L. Cabaret, C. Canali, R. Caravita, F. Castelli, G. Cerchiari, S. Cialdi, D. Comparat, G. Consolati, S. Di Domizio, L. Di Noto, M. Doser, A. Dudarev, A. Ereditato, R. Ferragut, A. Fontana, P. Genova, M. Giammarchi, A. Gligorova, S. N. Gninenko, S. Haider, S. D. Hogan, T. Huse, E. Jordan, L. V. Jørgensen, T. Kaltenbacher, J. Kawada, A. Kellerbauer, A. Knecht, D. Krasnický, V. Lagomarsino, S. Mariazzi, V. A. Matveev, F. Merkt, F. Moia, G. Nebbia, P. Nédélec, M. K. Oberthaler, N. Pacifico, V. Petráček, C. Pistillo, F. Prelz, M. Prevedelli, C. Regenfus, C. Riccardi, O. Röhne, A. Rotondi, H. Sandaker, P. Scampoli, J. Storey, M. A. S. Vasquez, M. Špaček, G. Testera, D. Trezzi, R. Vaccarone, S. Zavatarelli, Development of nuclear emulsions with 1 μ m spatial resolution for the aegis experiment. *Nucl. Instr. Meth. Phys. Res. A* **732**, 325–329 (2013).
- S. Aghion, O. Ahlén, C. Amsler, A. Ariga, T. Ariga, A. S. Belov, G. Bonomi, P. Bräunig, J. Bremer, R. S. Brusa, L. Cabaret, C. Canali, R. Caravita, F. Castelli, G. Cerchiari, S. Cialdi, D. Comparat, G. Consolati, J. H. Derking, S. Di Domizio, L. Di Noto, M. Doser, A. Dudarev, A. Ereditato, R. Ferragut, A. Fontana, P. Genova, M. Giammarchi, A. Gligorova, S. N. Gninenko, S. Haider, J. Harasimovic, S. D. Hogan, T. Huse, E. Jordan, L. V. Jørgensen, T. Kaltenbacher, J. Kawada, A. Kellerbauer, M. Kimura, A. Knecht, D. Krasnický, V. Lagomarsino, A. Magnani, S. Mariazzi, V. A. Matveev, F. Moia, G. Nebbia, P. Nédélec, M. K. Oberthaler, N. Pacifico, V. Petráček, C. Pistillo, F. Prelz, M. Prevedelli, C. Regenfus, C. Riccardi, O. Röhne, A. Rotondi, H. Sandaker, P. Scampoli, A. Sosa, J. Storey, M. A. S. Vasquez, M. Špaček, G. Testera, D. Trezzi, R. Vaccarone, C. P. Welsch, S. Zavatarelli, Prospects for measuring the gravitational free-fall of antihydrogen with emulsion detectors. *J. Instrum.* **8**, P08013 (2013).

23. C. Pistillo, S. Aghion, C. Amsler, A. Ariga, T. Ariga, A. Belov, G. Bonomi, P. Bräunig, J. Bremer, R. S. Brusa, L. Cabaret, M. Caccia, R. Caravita, F. Castelli, G. Cerchiari, K. Chlouba, S. Cialdi, D. Comparat, G. Consolati, A. Demetrio, H. Derking, L. Di Noto, M. Doser, A. Dudarev, A. Ereditato, R. Ferragut, A. Fontana, S. Gerber, M. Giammarchi, A. Gligorova, S. Gninenko, S. Haider, S. Hogan, H. Holmestad, T. Huse, E. J. Jordan, J. Kawada, A. Kellerbauer, M. Kimura, D. Krasnický, V. Lagomarsino, S. Lehner, C. Malbrunot, S. Mariazzi, V. Matveev, Z. Mazzotta, G. Nebbia, P. Nédélec, M. Oberthaler, N. Pacifico, L. Penasa, V. Petráček, F. Prelz, M. Prevedelli, L. Ravelli, C. Riccardi, O. Röhne, S. Rosenberger, A. Rotondi, H. Sandaker, R. Santoro, P. Scampoli, M. Simon, M. Špaček, J. Storey, I. M. Strojek, M. Subieta, G. Testera, E. Widmann, P. Yzombard, S. Zavatarelli, J. Zmeskal, Emulsion detectors for the antihydrogen detection in aegis. *Hyperfine Interact.* **233**, 29–34 (2015).
24. S. Aghion, O. Ahlén, A. S. Belov, G. Bonomi, P. Bräunig, J. Bremer, R. S. Brusa, G. Burghart, L. Cabaret, M. Caccia, C. Canali, R. Caravita, F. Castelli, G. Cerchiari, S. Cialdi, D. Comparat, G. Consolati, J. H. Derking, S. Di Domizio, L. Di Noto, M. Doser, A. Dudarev, R. Ferragut, A. Fontana, P. Genova, M. Giammarchi, A. Gligorova, S. N. Gninenko, S. Haider, J. Harasimowicz, T. Huse, E. Jordan, L. V. Jørgensen, T. Kaltenbacher, A. Kellerbauer, A. Knecht, D. Krasnický, V. Lagomarsino, A. Magnani, S. Mariazzi, V. A. Matveev, F. Moia, G. Nebbia, P. Nédélec, N. Pacifico, V. Petráček, F. Prelz, M. Prevedelli, C. Regenfus, C. Riccardi, O. Röhne, A. Rotondi, H. Sandaker, A. Sosa, M. A. Subieta Vasquez, M. Špaček, G. Testera, C. P. Welsch, S. Zavatarelli, Detection of low energy antiproton annihilations in a segmented silicon detector. *J. Instrum.* **9**, P06020 (2014).
25. N. Pacifico, S. Aghion, J. Alozy, C. Amsler, A. Ariga, T. Ariga, G. Bonomi, P. Bräunig, J. Bremer, R. S. Brusa, L. Cabaret, M. Caccia, M. Campbell, R. Caravita, F. Castelli, G. Cerchiari, K. Chlouba, S. Cialdi, D. Comparat, G. Consolati, A. Demetrio, L. Di Noto, M. Doser, A. Dudarev, A. Ereditato, C. Evans, R. Ferragut, J. Feseli, A. Fontana, S. Gerber, M. Giammarchi, A. Gligorova, F. Guatieri, S. Haider, H. Holmestad, T. Huse, J. E. Jordan, A. Kellerbauer, M. Kimura, D. Krasnický, V. Lagomarsino, P. Lansonneur, G. Lawler, P. Lebrun, X. Llopart, C. Malbrunot, S. Mariazzi, L. Marx, V. Matveev, Z. Mazzotta, G. Nebbia, P. Nédélec, M. K. Oberthaler, D. Pagano, L. Penasa, V. Petráček, C. Pistillo, F. Prelz, M. Prevedelli, L. Ravelli, L. Resch, O. Röhne, A. Rotondi, M. Sacerdoti, H. Sandaker, R. Santoro, P. Scampoli, L. Smeštad, F. Sorrentino, M. Špaček, J. Storey, I. Strojek, G. Testera, I. C. Tietje, L. Tlustos, E. Widmann, P. Yzombard, S. Zavatarelli, J. Zmeskal, N. Zurlo, Direct detection of antiprotons with the Timepix3 in a new electrostatic selection beamline. *Nucl. Instrum. Methods Phys. Res. A* **831**, 12–17 (2016).
26. H. Holmestad, *Data analysis, simulations, and reconstruction of antiproton annihilations in a silicon pixel detector*. PhD thesis, University of Oslo, Department of Physics 2018.
27. J. Timepix Poikela, T. W. Plosila, M. Campbell, M. De Gaspari, X. Llopart, V. Gromov, R. Kluit, M. Van Beuzekom, F. Zappone, V. Zivkovic, C. Brezina, K. Desch, Y. Fu, A. Kruth, Timepix3: A 65k channel hybrid pixel readout chip with simultaneous toa/tot and sparse readout. *J. Instrum.* **9**, C05013 (2014).
28. X. Llopart, J. Alozy, R. Ballabriga, M. Campbell, R. Casanova, V. Gromov, E. H. M. Heijne, T. Poikela, E. Santin, V. Sriskaran, L. Tlustos, A. Vitkovskiy, Timepix4, a large area pixel detector readout chip which can be tiled on 4 sides providing sub-200 ps timestamp binning. *J. Instrum.* **17**, C01044 (2022).
29. Sony Semiconductor Solutions Corporation, *Diagonal 4.60 mm (Type 1/4.0. 8 Mega-Pixel CMOS Image Sensor with Square Pixel for Color Cameras)* (2016).
30. R. Matthews, N. Falkner, M. Sorell, Reverse engineering the Raspberry Pi Camera v2: A study of pixel non-uniformity using a scanning electron microscope. *Forensic Sci. Int. Digit. Invest.* **32**, 200900 (2020).
31. M. Berghold, V. V. Burwitz, L. Mathes, C. Hugenschmidt, F. Guatieri, Imaging low-energy positron beams in real-time with unprecedented resolution. *Sci. Rep.* **13**, 18526 (2023).
32. T. B. Day, G. A. Snow, J. Sucher, High-orbital S-state capture of π^- mesons by protons. *Phys. Rev.* **118**, 864–866 (1960).
33. T. Von Egidy, Interaction and annihilation of antiprotons and nuclei. *Nature* **328**, 773–778 (1987).
34. J.-M. Richard, Antiproton physics. *Front. Phys.* **8**, 6 (2020).
35. M. R. Clover, R. M. DeVries, N. J. DiGiacomo, Y. Yariv, Low energy antiproton-nucleus interactions. *Phys. Rev. C* **26**, 2138 (1982).
36. T. Walcher, Experiments at the low-energy antiproton ring (LEAR). *Annu. Rev. Nucl. Part. Sci.* **38**, 67–95 (1988).
37. P. Hofmann, F. J. Hartmann, H. Daniel, T. Von Egidy, W. Kanert, W. Markiel, H. S. Plendl, H. Machner, G. Riepe, D. Protić, D. Protić, K. Zioc, R. Marshall, J. J. Reidy, Charged-particle spectra from antiproton annihilation at rest in $a = 12$ –238 nuclei. *Nucl. Phys. A* **512**, 669–683 (1990).
38. C. Amsler, F. Myhrer, Low energy antiproton physics. *Annu. Rev. Nucl. Part. Sci.* **41**, 219–267 (1991).
39. D. Polster, D. Hilscher, H. Rossner, T. von Egidy, F. J. Hartmann, J. Hoffmann, W. Schmid, I. A. Pshenichnov, A. S. Iljinov, Y. S. Golubeva, H. Machner, H. S. Plendl, A. Grochulka, J. Jastrzebski, W. Kurcewicz, P. Lubinski, J. Eades, S. Neumaier, Light particle emission induced by stopped antiprotons in nuclei: Energy dissipation and neutron-to-proton ratio. *Phys. Rev. C* **51**, 1167 (1995).
40. C. Amsler, Proton-antiproton annihilation and meson spectroscopy with the crystal barrel. *Rev. Mod. Phys.* **70**, 1293–1339 (1998).
41. C. Amsler, Nucleon-antinucleon annihilation at LEAR. arXiv:1908.08455 (2019).
42. F. Balestra, M. P. Busa, L. Busso, L. Ferrero, G. Gervino, A. Grasso, D. Panzieri, G. Piragino, F. Tosello, G. Bendiscioli, V. Filippini, G. Fumagalli, E. L. Rizzini, C. Marciano, A. Rotondi, A. Venaglion, A. Zenoni, C. Guaraldo, A. Maggiora, A. Cavestro, M. Vascon, G. Zanella, Y. K. Akimov, Y. A. Batusov, I. V. Falomkin, G. B. Pontecorvo, Experimental apparatus for studying the interaction of antiprotons with light nuclei. *Nucl. Instrum. Methods Phys. Res. A* **234**, 30–41 (1985).
43. G. Battistoni, T. Boehlen, F. Cerutti, P. W. Chin, L. S. Esposito, A. Fasso, A. Ferrari, A. Lechner, A. Empl, A. Mairani, A. Mereghetti, P. G. Ortega, J. Ranft, S. Roesler, P. R. Sala, V. Vlachoudis, G. Smirnov, Overview of the FLUKA code. *Ann. Nucl. Energy* **82**, 10–18 (2015).
44. S. E. Reichenbach, S. K. Park, R. Narayanswamy, Characterizing digital image acquisition devices. *Opt. Eng.* **30**, 170–177 (1991).
45. V. Sriskaran, J. Alozy, R. Ballabriga, M. Campbell, P. Christodoulou, E. Heijne, A. Koukab, T. Kugathasan, X. Llopart, M. Piller, A. Pulli, J.-M. Sallese, L. Tlustos, High-rate, high-resolution single photon x-ray imaging: Medipix4, a large 4-side buttable pixel readout chip with high granularity and spectroscopic capabilities. *J. Instrum.* **19**, P02024 (2024).
46. M. Volponi, S. Huck, R. Caravita, J. Zielinski, G. Kornakov, G. Kasprovicz, D. Nowicka, T. Rauschendorfer, B. Rienäcker, F. Prelz, M. Auzins, B. Bergmann, P. Burian, R. S. Brusa, A. Camper, F. Castelli, R. Ciurylo, G. Consolati, M. Doser, L. T. Glöggler, Ł. Graczykowski, M. Grosbart, F. Guatieri, N. Gusakova, F. Gustafsson, S. Haider, M. Janik, G. Khatri, Ł. Kłosowski, V. Krumins, L. Lappo, A. Linek, J. Malamant, S. Mariazzi, L. Penasa, V. Petracek, M. Piwiński, S. Pospisil, L. Povol, S. Rangwala, B. S. Rawat, V. Rodin, O. M. Röhne, H. Sandaker, P. Smolyanskiy, T. Sowiński, D. Tefelski, T. Vafeiadis, C. P. Welsch, T. Wolz, M. Zawada, N. Zurlo, Circus: An autonomous control system for antimatter, atomic and quantum physics experiments. *EPJ Quantum Technol.* **11**, 10 (2024).

Acknowledgments: We thank M. Fußeder and T. Schwarz-Selinger from the tandem accelerator lab of the Max Planck Institute for Plasma Physics (IPP) for granting us the beam time necessary to characterize proton interactions with the sensor. Then, M. Bömer and the electronics laboratory of the Physics Department of the technical University of Munich for the support in building our hardware. **Funding:** The AEGIS collaboration is funded by the Istituto Nazionale di Fisica Nucleare; the CERN Fellowship programme and the CERN Doctoral student programme; the EPSRC of UK under grant number EP/X014851/1; Research Council of Norway under grant agreement no. 303337 and NorCC; CERN-NTNU doctoral program; the Research University – Excellence Initiative of Warsaw University of Technology via the strategic funds of the Priority Research Centre of High Energy Physics and Experimental Techniques; the IDUB POSTDOC programme; the Narodowe Centrum Nauki under agreement nos. 2022/45/B/ST2/02029 and 2022/46/E/ST2/00255, and by the Polish Ministry of Education and Science under agreement no. 2022/WK/06; Wolfgang Gentner Programme of the German Federal Ministry of Education and Research (grant no. 13E18CHA); European Research Council under the European Unions Seventh Framework Program FP7/2007-2013 (grants nos. 291242 and 277762); the European Social Fund within the framework of realizing the project, in support of intersectoral mobility and quality enhancement of research teams at Czech Technical University in Prague (grant no. CZ.1.07/2.3.00/30.0034); the Ministry of Culture and Research of the State of North Rhine-Westphalia; the Polish National Science Centre under agreement no. 2023/50/E/ST2/00574; and the European Union's Horizon Europe research and innovation programme, under grant no. 101109574. **Author contributions:** M.B. and F. G. planned the investigation, configured the sensor, ran the measurements and wrote the analysis code. Them and D. O. wrote the paper. The rest of the authors designed, built, maintained, and operated the AEGIS apparatus during the execution of the measurement; contributed, discussed, and corrected the data analysis; and corrected the drafts of the paper. **Competing interests:** The authors declare that they have no competing interests. **Data and materials availability:** Sufficient information to evaluate the correctness of the analysis and conclusions is present in the text.

Submitted 2 August 2024
 Accepted 26 February 2025
 Published 2 April 2025
 10.1126/sciadv.ads1176